

Soil Scientists • Engineers • Waste Water Professionals Markham D. Smith, A.O.S.E., L.P.S.S.,

8399 West Main Street, Marshall, Virginia 20115 (540) 364-1122 10805 MAIN STREET, SUITE 700, FAIRFAX, VIRGINIA 22030 (703) 662-5398 F. (540) 364-2060 SOILS-INC.COM

February 6, 2019

Classic Cottages, LLC 433 East Monroe Avenue Alexandria, Virginia 22301

Attn: Ms. Elainna Wright

Re: Groundwater Table and Bedrock Evaluation Report 4219 Lorcom Lane Arlington, Virginia Project No. T1786

Dear Ms. Wright,

As requested, Soils, Inc. conducted a water table and bedrock investigation at your above referenced project. The study was completed on January 25, 2019. The investigation included a review of the site plan provided by Walter L. Phillips and a site visit to advance six (6) hand auger borings. The hand auger borings were advanced to investigate the soil for potential restrictions that could limit the use of the proposed stormwater management facilities. The borings were advanced to a depth of 120 inches with the exception of boring P-4, in which auger refusal was encountered at a depth of 97 inches due to quartz gravel.

A Static Cone Penetrometer (SCP) was used during drilling to evaluate the density of the underlying soils. Based on the results of SCP testing at depths of 9 and 10 feet, no bedrock was encountered in any of the borings.

No Seasonal High Water Table (SHWT) indications were identified in any of the borings. What appeared to be existing fill material was encountered at the existing ground surface in boring P-1, P-2 and P-4 extended to depths of 31 to 75 inches. The USDA soil profile descriptions and the boring location sketch are attached.


Soils, Inc. thanks you for the opportunity to perform this work. If you have any questions regarding this letter or if any additional fieldwork is required, please do not hesitate to contact us.

#### Sincerely,




Markham D. Smith, L.P.S.S. # 3401000243 President


Soil Profile Description Report (USDA) Boring location Sketch



ARLINGTON, VIRGINIA

CLIENT: CLASSIC COTTAGES, LLC





# **TECHNICAL DATA SHEET NONWOVEN GEOTEXTILE** encountered mildew, insects and soil chemicals, and is non-biodegradable.

\* OR EQUIVALENT

GEOSYNTHETICS

N040 is a polypropylene, needle punched nonwoven geotextile for use in drainage and separation applications. It has been stabilized to resist degradation due to ultraviolet exposure and is resistant to commonly

PROPERTY	TEST METHOD	TYPICAL ROLL VALUI
Grab Tensile Strength <sup>1</sup>	ASTM D4632	100 lbs
Grab Tensile Elongation	ASTM D4632	50%
CBR Puncture	ASTM D6241	280 lbs
Trapezoid Tear Strength	ASTM D4533	50 lbs
UV Resistance @ 500 hrs	ASTMD4355	70%
Apparent Opening Size (AOS)	ASTM D4751	70 US Sieve
Permittivity (sec¹)	ASTM D4491	2.0 (sec1)
Flow Rate	ASTM D4491	140 gpm/ft²


Values quoted above are the result of multiple tests conducted at an independent testing facility. N040 meets or exceeds values listed. <sup>1</sup>Values apply to both machine and cross-machine directions

PACKAGING: Roll Width	12.5 ft.	15 ft.	
Roll Length	360 ft.	360 ft.	
Roll Area	500 yd²	600 yd²	

Disclaimer: ACF Environmental assumes no liability for the completeness or accuracy of this information or the ultimate use of this information. This document should not be construed as engineering advice. Always consult the project engineer for project specific requirements. The end user assumes sole responsibility for the use of this information and product.



### 3" and 4" Pop-Up Drainage Emitter with Elbow and Universal Adapter



Part #: 430 Material: High Density Polypropylene (HDPE) Load Recommendation Guide Colors: Green Fits: 3" and 4" corrugated, sewer, triple wall pipe and 4" Sch. 40 pipe Class A Open Surface Area: 10 Sq. Inches Loads of 1-60 psi. Spring: Stainless Steel Grade 302 Recommended for pedestrians, bicycles and wheel Open Pressure: 0.04 PSI

Flow Rate:

UV inhibitor

1" Head: 43.26 G.P.M

0.5" Head: 30.59 GPM

Elbow: 1/4" drain hole

MDS

## Visit ndspro.com for specs,

#### NOTE: PERVIOUS ASPHALT IS NOT AN ACCEPTABLE OPTION IN ARLINGTON COUNTY

Permeable pavement block systems require edge restraints to prevent movement of the pavement blocks. Edge restraints may be standard VDOT curbs, standard VDOT combination curb and gutters, or precast or cast in place reinforced concrete borders a minimum 6 inches wide and 18 inches deep constructed with Class A3 concrete. Edge restraints shall be installed flush with the paver blocks. Permeable pavement block systems used for residential driveways, walkways, and patios can be installed using plastic edge restraints.

Installation of permeable interlocking pavers should only be performed by qualified personnel. A PICP specialist designee should be on site, overseeing each placement crew, during all paver placement and finishing operations.

Pervious Concrete work shall conform to all requirements of ACI 522.1, "Specification for Pervious Concrete Pavement" published by the American Concrete Institute.

Installation of pervious concrete should only be performed by qualified personnel. A National Ready Mixed Concrete Association (NRMCA) Certified Pervious Concrete Craftsman or Installer should be on site, overseeing each placement crew, during all concrete placement and finishing operations. Each placement crew should have at least two NRMCA certified Pervious Concrete Technicians (per ACI 522.1-13).

### PERMEABLE PAVER DESIGN

DESIGN INFITLRATION RATE = 0.50 IN/HR

GRAVEL POROSITY = 0.40

LEVEL 1 Tv = 1 inch depth

						VOLUME		
	DESIGN	IMPERVIOUS	MIN. REQ.	SURFACE AREA	GRAVEL DEPTH	PROVIDED	MAX DRAWDOWN	
FACILITY	LEVEL	DRAINAGE AREA (SF)	TV (CF)	PROVIDED (SF)	(TREATMENT) (FT)	(TREATMENT) (CF)	TIME (HRS)	UNDERDRA
A1 DRIVEWAY	1	475	38	475	1.0	190	9.6	NO
A1 PATIO	1	135	11	135	1.0	54	9.6	NO
<b>A1 LEADWALK</b>	1	125	10	125	1.0	50	9.6	NO
<b>B1 DRIVEWAY</b>	1	475	38	475	1.0	190	9.6	NO
<b>B1 PATIO</b>	1	135	11	135	1.0	54	9.6	NO
<b>B1 LEADWALK</b>	1	125	10	125	1.0	50	9.6	NO

### PERMEABLE PAVEMENT MAINTENANCE

#### Permeable Pavement Maintenance Schedule

sediment or erosion.

Maintenance Activity				
•	Check observation wells 3 days after a storm event in excess of 1/2 inch in depth. Standing water observed in the well after three days is a clear indication of clogging.	Annually		
•	Inspect the surface of the permeable pavement for evidence of sediment deposition, organic debris, staining or ponding that may indicate surface clogging. If any signs of clogging are noted, schedule a vacuum sweeper (no brooms or water spray) to remove deposited material.			
•	Inspect the structural integrity of the pavement surface, looking for signs of surface deterioration, such as slumping, cracking, spalling or broken pavers.  Replace or repair affected areas, as necessary.			
•	Check inlets, pretreatment cells and any flow diversion structures for sediment buildup and structural damage. Note if any sediment needs to be removed.			

#### PERMEABLE PAVEMENT MATERIAL SPECS

Inspect the condition of the observation well and make sure it is still capped.

Inspected and certified by a professional licensed in the State of Virginia

Generally inspect any contributing drainage area for any controllable sources of

Once every 5

years

Material Specifications for Underneath the Permeable Pavements

Material	Specification	Notes				
Bedding Layer	PC: None PICP: 2 in. depth of No. 8 stone above 4 inches of No. 57	ASTM D448 size No. 8 stone (e.g. 3/8 to 3/16 inch in size). ASTM D448 size No. 57 stone (e.g. 1 1/2 to 1/2 inch in size) Should be double-washed and clean and free of all fines.				
Reservoir Layer	PC: No. 57 stone PICP: No. 2 or 3 stone	PC: ASTM D448 size No. 57 stone (e.g. 1 1/2 to 1/2 inch in size) PICP: No. 2 Stone (e.g. 3 inch to 3/4 inch in size) or No. 3 Stone. Depth is based on the pavement structural and hydraulic requirements. Should be double-washed and clean and free of all fines.				
Underdrain	Use 4 to 6 inch diameter perforated PVC (AASHTO M 252) pipe, with 3/8-inch perforations at 6 inches on center; each underdrain installed at a minimum 0.5% slope located 20 feet or less from the next pipe (or equivalent corrugated HDPE may be used for non-vehicular applications). Perforated pipe installed for the full length of the permeable pavement cell, and non-perforated pipe, as needed, is used to connect with the storm drain system. T's and Y's installed as needed, depending on the underdrain configuration. Extend cleanout pipes to the surface with caps.					
Filter Layer	The underlying native soils should be separated from the stone reservoir by a 2 to 4 inch layer of choker stone (e.g. No. 8) covered by a 6 to 8 inch layer of coarse sand (e.g. ASTM C 33, gradation) or use an appropriate filter fabric for the particular application based on AASHTO M288-06. At a minimum the fabric shall have a Flow Rate greater than 125 gpm/sq. ft. (ASTM D4491), and an Apparent Opening Size (AOS) equivalent to a US # 70 or # 80 sieve (ASTM D4751). The geotextile AOS selection is based on the percent passing the No. 200 sieve in "A" Soil subgrade, using FHWA or AASHTO selection criteria.					
Observation Well	Use a perforated 4 to 6 inch vertice installed flush with the surface. Applications of the surface in the surfa	al PVC pipe (AASHTO M 252) with a cap, oplications in vehicular areas shall have a				

Observation Well installed flush with the surface. Applications in vehicular areas shall have a metal cap. All applications shall have an observation well installed.

<u>Construction Installation</u>. The installation and inspection of the construction of permeable pavement is to follow the Construction Inspection Checklist. The checklist is to be included on

\*PC: Permeable Concrete, PICP: Permeable Interlocking Concrete Pavers

### **SECTION 8: CONSTRUCTION**

Experience has shown that proper installation is absolutely critical to the effective operation of a permeable pavement

#### 8.1 Necessary Erosion & Sediment Controls


the plan (Appendix G).

- All permeable pavement areas should be fully protected from sediment intrusion by silt fence or construction fencing, particularly if they are intended to infiltrate runoff.
- Permeable pavement areas should remain outside the limit of disturbance during construction to prevent soil compaction by heavy equipment. Permeable pavement areas should be clearly marked on all construction documents and grading plans. To prevent soil compaction, heavy vehicular and foot traffic should be kept out of permeable pavement areas during and immediately after construction.
- During construction, care should be taken to avoid tracking sediments onto any permeable pavement surface to avoid
- Any area of the site intended ultimately to be a permeable pavement area should generally not be used as the site of a temporary sediment basin. Where locating a sediment basin on an area intended for permeable pavement is unavoidable, the invert of the sediment basin must be a minimum of 2 feet above the final design elevation of the bottom of the aggregate reservoir course. All sediment deposits in the excavated area should be carefully removed prior to installing the sub-base, base and surface materials.

#### WATER PROOFING NOTES

NOTE: WALTER L. PHILLIPS, INC. IS NOT RESPONSIBLE FOR WATER PROOFING DESIGN REQUIRED AT BUILDING FOUNDATION. CONTRACTOR AND OWNER TO PROVIDE PROPER WATERPROOFING ESPECIALLY NEAR PROPOSED BMP FACILITIES.

ARLINGTON COUNTY DOES NOT REVIEW THE WATERPROOFING DESIGN AND THE OWNER/DEVELOPER AGREES TO HOLD ARLINGTON COUNTY HARMLESS IN THE EVENT OF FAILURE.



## **BMP DETAILS - PERMEABLE PAVEMENT**



Engineers • Surveyors • Planners Landscape Architects • Arborists 207 PARK AVENUE

FALLS CHURCH, VIRGINIA 22046 (703) 532-6163 Fax (703) 533-1301

#### ARLINGTON, VIRGINIA DEPARTMENT OF ENVIRONMENTAL SERVICES

**4219/4221 LORCOM LANE** 

THE PROPERTY OF R.A. PHILLIPS **GRADING PLAN** 

4219/4221 LORCOM LANE, ARLINGTON, VIRGINIA 22207

LE: 1" = 10'	DRAWN (	CR C		CHECKED TPB/KW		
MITTED DATE 03/05/2019 05/07/2019 06/24/2019	) 					
07/17/2019				A	PPROVED	DATE
				D	DIRECTOR O	F ENVIRONMENTAL SERVICES
			SHEET: C-07	704		

SCALE: NTS

SI PROJECT#: T1786